

• ടെണ്ടർ (Tender)

- (352/25-26): പഞ്ചായത്ത് ഓഫീസ് ഒന്നാം നില നെറ്റ് വർക്കിംഗ്
- (370/25-26): പഞ്ചായത്ത് മീറ്റിംഗ് ഹാളിൽ സൗണ്ട് സിസ്റ്റം സ്ഥാപിക്കൽ

Important Dates

- Last date for tender form supply: 02-07-2026 3pm
 - Receiving of tender: 04-07-2026 at 2:00 PM
 - Opening of tender: 04-07-2026 at 3:00 PM


TECHNICAL SANCTION FOR WORKS

LSGD DIVISION KANNUR, ELECTRONICS TECHNICAL COMMITTEE

ORDER No. 05/2025-26 (8) Dated 23/02/2026

Name of Work	Annual Plan 2025-26 - Project No. 352/26-Supply and Installation of Local Area Network (LAN) in the first floor of Malur Grama Panchayat Office.	
Duration of Work		
Amount for which Technical Sanction Issued	1,80,000/-	
Reference in Administrative Sanction		
1.	Number	352/26
	Date	
	Amount	1,80,000/-
	Source of Fund	Own Fund

Technical Sanction issued for the above work is entered in the Technical Sanction Register vide Register Number 05/2025-26(8) Dated 23/02/2026.


Executive Engineer
Convener, Electronics Technical Committee

LOCAL SELF GOVERNMENT DEPARTMENT

ELECTRONICS ESTIMATE

Name of work: Annual Plan 2025-26 - Project No. 352/26 - Supply and Installation of Local Area Networking (LAN) at First Floor of Malur Grama Panchayat Office

Sl No.	Description	Unit	Qty	Rate	Amount
1	Supply and Installation of Fully loaded 24 port Patch panel with removable CAT-6 Keystone Jack, in the existing Rack for terminating CAT-6 cable from Information outlets. Preferred Make: Molex , Honeywell, 3C3 ,Comscope	No	1	5,790.00	5,790.00
2	Supply and installation 19", 9U wall mounted rack with 500mm depth and having front glass door& rear Ms doors, fitted with cooling fan , and 1 set of ISI standard Rack mountable AC distribution box with 6Nos. of 6A, 3 pin AC socket , 1U Closed Loop Cable manager . Preferred Make: Netrack, Dlink , MRS .	No	1	8,900.00	8,900.00
3	Supplying and fixing of following sizes of ISI standard PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same incase of recessed conduit as required (20 mm) Preferred Make: Eversine , Balco , Pricission.	Mtr	160	110.00	17,600.00
4	Supply and Installation of Rack Mountable semimanagable , 10/100/1000 Mbps, 24 port, Giga Ethernet Switch with 2 SFP GBIC fiber port , the existing 19" Rack. Preferred Make: Cisco, Netgear , HP	No	1	21,900.00	21,900.00
5	Supply, laying of CAT-6 4 pair 23Awg Lszh UTP Cable through the existing PVC conduit for the connection of Network point to Network Switch. Preferred Make: Molex , Honeywell , Comscope , 3C3	Mtr	600	60.00	36,000.00
6	Supply and fixing of 75mm x 75mm x 75 mm. deep PVC Backbox in recess, fixing one module face plate with CAT-6 RJ45 Jack (Group A) and making good the surface, painting /colour washing etc. as required including labour charges. Preferred Make: Molex, Honeywell, 3C3 ,Comscope.	No	16	415.00	6,640.00
7	Supplying and fixing of following sizes of ISI standard PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same incase of recessed conduit as required. (25 mm) Preferred Make: Eversine , Balco , Pricission.	Mtr	100	120.00	12,000.00
8	Supply and Providing 1 meter Lszh CAT-6 patch cord . Preferred Make:- Molex , 3C3 , Honeywell , Comscope.	No	20	190.00	3,800.00
9	Supply and installation of AX 1800 Wifi Dual band Celing mount access point 2.4/5Ghz ,1201mbps For 5Ghz , 574 Mbps for 2.4Ghz, with Hardware Controller support , Giga ethernet Port , POE Supported. Preferred Make: TP Link , Netgear , HP .	No	2	13,900.00	27,800.00
10	Supply and Providing 2 meter LSZH CAT-6 patch cord . Preferred Make:- Molex , Honeywell , 3C3 , Comscope.	No	20	245.00	4,900.00
11	Terminating the cables in the existing Patch panel, or terminating with RJ45 connector, testing each and every node point and making permanent labeling at the I/O and on the Patch panel.	No	1	3,500.00	3,500.00
Total Work done					148,830.00
GST @ 18%					26,789.00
Honorarium for Enpanelled Electronics Engineers@2.5% (0.5%+1.5%+0.5%) as per Para 3.8.4(B) of G.O. No. 86/2022/LSGD dated 19/04/2022					4,232.00
Contingencies					149.00
Grand Total					180,000.00
(Rupees One Lakh and Eighty Thousand only)					

TS No: 05/2025-26 (S) dt 23/12/26
for Rs. 1,80,000/-

EXECUTIVE ENGINEER
LID & EW (LSGD) DIVISION
KANNUR - 670002

MUKUNDAN. P.P
PANEL ENGINEER (ELECTRONICS)
DIST. PANCHAYATH, KANNUR
MOB: 9446043937

SAJEEVAN P.R, MIE, MIETE
PANEL ENGINEER (ELECTRONICS)
DIST. PANCHAYATH, KANNUR
Mob: 9446312385


TECHNICAL SANCTION FOR WORKS

LSGD DIVISION KANNUR, ELECTRONICS TECHNICAL COMMITTEE

ORDER No. 04/2025-26 (8) Dated 23/02/2026

Name of Work	Annual Plan 2025-26 - Project No. 370/26-Supply and Installation of Sound System in Meeting Hall of Malur Grama Panchayat	
Duration of Work		
Amount for which Technical Sanction Issued	3,00,000/-	
Reference in Administrative Sanction		
1.	Number	370/26
	Date	
	Amount	3,00,000/-
	Source of Fund	Own Fund

Technical Sanction issued for the above work is entered in the Technical Sanction Register vide Register Number 04/2025-26(8) Dated 23/02/2026.



Executive Engineer
Convener, Electronics Technical Committee

LOCAL SELF GOVERNMENT DEPARTMENT
ELECTRONICS ESTIMATE

Name of work: Annual Plan 2025-26 - Project No.370/26- Supply and installation of Sound System in Meeting Hall of Málur Grama Panchayath

Sl No.	Description	Unit	Qty	Rate	Amount
1	Supply and Providing 250 Watts PA Amplifier with 6 Nos. Mic Inputs, 2 Nos. Aux. Input, Freequency resonse 50-15000Hz +3 dB, Bass & Treble controls, Signal to Noise Ration: 60dB, Output : 4, & 8 hms, 70V & 100V outputs for each zone, MP3 Player with USB, SD, MIMC card reader, Bluetooth and Remote control, suitable for AC & 24 VDC operation. Preferred Model Ahuja SSA 250DP.	No	1	21,900.00	21,900.00
2	Supply and Providing Dual Wireless Microphone of single channel of non-diversity, freequency response 50Hz to 16 KHz, balance XLR output. Preferred Model : Studio master XR-40HH.	No	1	9,500.00	9,500.00
3	Supply and Providing 6 Channel PA Mixer with Mic Input, Line Input, Tone controls, Freequency resone 25 Hz to 25 KHz, Digital signal processing features, MP3 Player, Recorder with USB Reader and Blue tooth . Preferred Model :Ahuja FMX-106DP	No	1	8,950.00	8,950.00
4	Supply and Providing of PA Wall mount Speaker of 6 inch woofer, 1 inch tweeter, Power taps 60/30/15/7.5 Watts at 8,ohm with all accessories. Preferred Model : Studio Master ARC 60	No	4	10,900.00	43,600.00
5	Supply and Providing of speaker cable 2x 1.5 sqmm cable laying through existing conduit. Preferred Model : Hawels , Finolex	No	100	60.00	6,000.00
6	Supply and Providing PA Microphone Floor Stand of height 920-1500mm, Base Dia. 230mm, weight 4.60Kg. Preferred Model :Ahuja DGN	No	1	1,925.00	1,925.00
7	Supply and fixing of 20 mm rigid PVC conduit ivory with ISI conforming to ISI standard with all accessories.Prifferd Make : Evershine , Soorya	No	100	98.00	9,800.00
8	Supply and installation of unidirectional Dynamic Microphone Frequency Response 20-16,000Hz, Sensitivity 3.15mv/Pa, Impedance 350 ohm. With 3 pin XLR connector and 10 meter low noise shielded 2 core Mic cable. Preferred model: Ahuja PRO-3400 plus .	No	1	5,900.00	5,900.00
9	Supply and Providing Inter Connecting cables, PC to Amplifier Cable, jack to jack cable, connecting cables from Mixer to Amplifier	Set	1	3,350.00	3,350.00
10	Supply and Providing 700x 600 mm Floor Mount wooden Rack with mooving tray 6 Socket PDU and accessories, Audio device, interconnecting cables.	No	1	13,500.00	13,500.00
11	Supply and Installation of commercial grade Interactive Panel Size 75" 4K altra clear visual screen Touch CPU Core Cortex A73x4, 8 GB Ram, 128GB Rom, Android 14 OS, 20 writing point simulatancosuly , Multi user can write draw and mark, 16:9 aspect ratio , Brightness with glass min 400 nits , 3xHDMI in 1xHDMI out, 2xUSB 2.0 and Type C,2x USB 3.0 , RJ 45 in and Out , VGA, High speed da ta transmission, Sleek & Slim appearance, Touch Finger and passive infrared pen, Optional for Windows OPS, Connecting option for Lap/PC . 3 Year warranty .Preferd Make: Benq , Logic , LG	No	1	124,500.00	124,500.00
Total					248,925.00
GST @ 18%					44,807.00
Honorarium for Empanelled Electronics Engineers@2.5% (0.5%+1.5%+0.5%) as per para 3.8.4(B) of G.O. No. 84/2022/LSGD dated 19/04/2022					6,223.00
Contigencies					45.00
Grand Total					300,000.00
(Rupees Three Lakhs only)					

TS No. 04/2025-26 (S) Dt 23/2/2026
for Rs. 3,00,000/-

EXECUTIVE ENGINEER
LID & EW (LSGD) DIVISION
KANNUR - 670002

MUKUNDAN. P.P
PANEL ENGINEER (ELECTRONICS)
DIST. PANCHAYATH, KANNUR
MOB: 9446043937

SAJEEVAN P.R. MIE. MIETE
PANEL ENGINEER (ELECTRONICS)
DIST. PANCHAYATH, KANNUR
Mob: 9446312385